Effective July 27, 2017

P90L 6kVA & 10kVA Series UPS Price List

*For the most current pricing, visit www.xpcc.com/pricing

Online 6kVA & 10kVA
208/230VAC or 208:240/120VAC

Reduce power consumption and increase end to end efficiency with this powerful single-phase UPS

- 98% efficient operation
- Smart LCD display
- Multiple communications capability
- Programmable outlets
- 2A and 4A charger models available
- $50,000 load protection policy
- UL, cUL, RoHS, CE
- 3 years electronics, 3 years battery warranty (USA and Canada)

P90L 6kVA 208/230VAC Bundle Pricing

P90L-6KB*X* bundles include battery pack and 4-post rail kits. Standard 2A charger model.

Model	Part Number	Description	List Price	Input Power Cord	Output Receptacles	Total Weight	Rack Space
P90L-6KB	90000830	6kVA/5.4kW UPS 208/230V	$4,399.00	Terminal block with L6–30P, 6ft	Terminal block with L6–30R, 3ft	230 lbs	6U
P90L-6KB2	90000832	6kVA/5.4kW UPS 208/230V	$4,788.00	Terminal block with L6–30P, 6ft	(2) L6–30R + (2) L6–20R + (4) 6–15/20R	239 lbs	6U
P90L-6KB3	90000833	6kVA/5.4kW UPS 208/230V	$4,788.00	Terminal block with L6–30P, 6ft	(2) L6–30R + (4) L6–20R	238 lbs	6U
P90L-6KB4	90000834	6kVA/5.4kW UPS 208/230V	$4,698.00	Terminal block with L6–30P, 6ft	(4) IEC C19 + (8) IEC C13	236 lbs	6U

P90L 6kVA 208:240/120VAC Bundle Pricing

P90L-6KTB*X* bundles include battery pack, isolation transformer, and 4-post rail kits. Standard 2A charger model.

Model	Part Number	Description	List Price	Input Power Cord	Output Receptacles	Total Weight	Rack Space
P90L-6KTB	90000835	6kVA/5.4kW UPS 208V:240/120V Isolation/Bypass	$6,324.00	Terminal block with L6–30P, 6ft	Terminal block	334 lbs	8U
P90L-6KTB1	90000836	6kVA/5.4kW UPS 208V:240/120V Isolation/Bypass	$6,449.00	Terminal block with L6–30P, 6ft	(1) L14–30R	335 lbs	8U
P90L-6KTB3	90000838	6kVA/5.4kW UPS 208V:240/120V Isolation/Bypass	$6,793.00	Terminal block with L6–30P, 6ft	(2) L6–30R + (4) L6–20R + (12) 5–15/20R	345 lbs	8U
P90L-6KTB4	Bundle	6kVA/5.4kW UPS and XPD-IT60A Bundle 208/120V Output	$5,823.00	Terminal block with L6–30P, 6ft	(1) L6-30R, (12) 5–15/20R	372 lbs	8U

P90L 10kVA 208/230VAC Bundle Pricing

P90L-10KB*X* bundles include battery pack and 4-post rail kits. Standard 2A charger model.

Model	Part Number	Description	List Price	Input Power Cord	Output Receptacles	Total Weight	Rack Space
P90L-10KB	90000840	10kVA/9kW UPS 208/230V	$5,449.00	Terminal block	Terminal block	235 lbs	6U
P90L-10KB2	90000842	10kVA/9kW UPS 208/230V	$5,838.00	Terminal block	(2) L6–30R + (4) L6–20R	242 lbs	6U
P90L-10KB3	90000843	10kVA/9kW UPS 208/230V	$5,748.00	Terminal block	(4) IEC C19 + (8) IEC C13	242 lbs	6U

P90L 10kVA 208:240/120VAC Bundle Pricing

P90L-10KTB*X* bundles include battery pack, isolation transformer with maintenance bypass, and 4-post rail kits. Standard 2A charger model.

Model	Part Number	Description	List Price	Input Power Cord	Output Receptacles	Total Weight	Rack Space
P90L-10KTB	90000844	10kVA/9kW UPS 208V:240/120V Isolation/Bypass	$8,474.00	Terminal block	Terminal block	362 lbs	9U
P90L-10KTB2	90000846	10kVA/9kW UPS 208V:240/120V Isolation/Bypass	$8,943.00	Terminal block	(2) L6–30R + (4) L6–20R + (12) 5–15/20R	372 lbs	9U

P90L 6kVA & 10kVA 208V 50/60Hz Component Pricing

P90L 6kVA & 10kVA Series come in both 2A or 4A chargers and no internal batteries. For applications requiring 3 or more battery packs, use "KH" models.

Model	Part Number	Description	List Price	Input Power Cord	Output Receptacles	Weight	Unit & Shipping Dimensions (W x D x H)
P90L-6K	90000930	6kVA/5.4kW 208/230V UPS Module with 2A 240V Nominal Charger, 3U	$2,849.00	Terminal block with L6–30P, 6ft	Terminal block with L6–30R, 3ft	55 lbs	17.3" x 26.3" x 5.3" 23.0" x 34.0" x 10.5"
P90L-6KH	90000140	6kVA/5.4kW 208/230V UPS Module with 4A 240V Nominal Charger, 3U	$3,049.00	Terminal block with L6–30P, 6ft	Terminal block with L6–30R, 3ft	55 lbs	17.3" x 26.3" x 5.3" 23.0" x 34.0" x 10.5"
P90L-10K	90000931	10kVA/9kW 208/230V UPS Module with 2A 240V Nominal Charger, 3U	$3,899.00	Terminal block	Terminal block	60 lbs	17.3" x 29.5" x 5.3" 23.5" x 34.5" x 10.0"
P90L-10KH	90000141	10kVA/9kW 208/230V UPS Module with 4A 240V Nominal Charger, 3U	$4,099.00	Terminal block	Terminal block	60 lbs	17.3" x 29.5" x 5.3" 23.5" x 34.5" x 10.0"
P90L-BP240	90000932	240V Battery Pack for P90L-6K, P90L-10K, 3U	$1,300.00	N/A	N/A	165 lbs	17.3" x 25.1" x 5.3" 23.0" x 34.0" x 10.5"

P90L Isolation Transformers

Model	Part Number	Description	List Price	Weight	Unit Dimensions (W x D x H)
XPD-IT60A	90000407	6kVA PDU with Isolation Transformer 208V to 120V (or 240V to 120V), 3ft L6–30P Input Cord, (1) L6–30R and (12) 5–15/20R Receptacles, Max. 120V load is 4kW.	$1,369.00	137 lbs	19.0" x 18.0" x 3.5"
P90L-ISO6MB	90000193	Isolation Transformer with Maintenance Bypass for use with P90L-6K for 240/120V Output with 1ft L6–30P	$1,800.00	99 lbs	17.3" x 28.7" x 3.5"
P90L-ISO6P	90000195	Isolation Transformer with Maintenance Bypass for use with P90L-6K for 240/120V Output. Includes L14–30R and 1ft Output Cord	$1,925.00	101 lbs	17.3" x 28.7" x 3.5"
P90L-ISO10MB	90000194	Isolation Transformer with Maintenance Bypass for use with P90L-10K for 240/120V Output	$2,900.00	122 lbs	17.3" x 31.8" x 5.2"

P90L Mounting Kits

Model	Part Number	Description	List Price	Weight	Unit Dimensions (W x D x H)
P90L-RAIL	90000933	4-Post Rail Kit	$125.00	5 lbs	3.8" x 19.8" x 2.8"
XPC-2POSTL	90000116	2-Post Shelf Kit; Rated for 150 lbs	$139.00	9 lbs	21.5" x 23.3" x 3.5"
XPC-2POST	90003042	Heavy Duty 2-Post Shelf Kit; Rated for 300 lbs	$250.00	14 lbs	19.0" x 29.0" x 5.2"

P90L Connectivity

Model	Part Number	Description	List Price	Unit Weight	Shipping Dimensions (W x D x H)
SNMP-2PMINI	90000399	Two Port Internal SNMP Card	$259.00	1 lb	7.25" x 6" x 2.5"
SNMP-EMD*	90000398	Environmental Monitoring Sensor	$149.00	1 lb	7.25" x 6" x 2.5"
MODBUS-IN	90000267	Modbus Card	$299.00	1 lb	7.25" x 6" x 2.5"
RELAY-MINI	90000265	General Relay Contacts with DB9 & Terminal Block Adapter	$110.00	1 lb	7.25" x 6" x 2.5"

**SNMP-EMD to be used with SNMP-2PMINI*

Power Distribution Units

Model	Part Number	Description	List Price	Input Power Cord	Outlets	Weight	Unit Dimensions (W x D x H)
XPD24C13V	90000374	30A 208V Basic PDU	$249.00	L6–30P, 6ft	(24) IEC C13	12.0 lbs	66.0" x 1.75" x 1.75"
XPD31	90000251	30A 240V 2U 19" Basic Rack PDU	$389.00	L6–30P, 6ft	(2) L6–30R + (2) L6–20R + (4) 6–15/20R	9.0 lbs	19.0" x 4.7" x 3.5"
XPD32	90000252	30A 240V 2U 19" Basic Rack PDU	$389.00	L6–30P, 6ft	(2) L6–30R + (4) L6–20R	7.5 lbs	19.0" x 2.4" x 3.5"
XPD33	90000253	30A 240V 2U 19" Basic Rack PDU	$299.00	L6–30P, 6ft	(4) IEC C19 + (8) IEC C14	6.0 lbs	19.0" x 2.4" x 3.5"
XPD34	90000254	30A 240/120V 2U 19" Basic Rack PDU	$469.00	L14–30P, 6ft	(2) L6–30R + (4) L6–20R + (12) 5–20R	9.5 lbs	19.0" x 4.7" x 3.5"
XPD35	90000255	50A 240V 2U 19" Basic Rack PDU	$389.00	Pigtail 2W+G	(2) L6–30R + (4) L6–20R	7.0 lbs	19.0" x 2.4" x 3.5"
XPD36	90000256	50A 240V 2U 19" Basic Rack PDU	$299.00	Pigtail 2W+G	(4) IEC C19 + (8) IEC C13	6.8 lbs	19.0" x 2.4" x 3.5"
XPD37	90000257	50A 240/120V 2U 19" Basic Rack PDU	$469.00	Pigtail 3W+G	(2) L6–30R + (4) L6–20R + (12) 5–20R	10.0 lbs	19.0" x 4.7" x 3.5"

Bypass Distribution Modules

Model	Part Number	Description	List Price	Utility Input	Output Connections	UPS Connections	Weight	Unit Dimensions (W x D x H)
XBDM-HW63	90000934	63A/230VAC Bypass Distribution Module	$450.00	Hardwire or optional cable kit	Hardwire terminal block	Hardwire or optional cable kit	7.1 lbs	17.25" x 5.25" x 3.5"

P90L Startup/Service Plans (USA and Canada)

On-site service within 100 miles of an Xtreme Power Service Technician. Contact inside sales for locations exceeding 100 miles.

Model	Part Number	Description	List Price
P9OS3610	90000348	On-site 3 Year Service Plan for P90L-6K, P90L-10K	$2,600.00
P9OS5610	90000349	On-site 5 Year Service Plan for P90L-6K, P90L-10K	$5,900.00
P9SP610	90000350	Extended 5 Year Factory Warranty for P90L-6K, P90L-10K	$1,500.00
P9SU58610	90000351	Startup 5 x 8 for first P90L-6K, P90L-10K	$1,800.00
P9SUAD	90000352	Startup 5 x 8 for each additional P90L-6K, P90L-10K	$900.00
P9PM610	90000353	Preventative Maintenance visit for first P90L-6K, P90L-10K	$1,800.00
P9PMAD	90000354	Preventative Maintenance visit for each additional P90L-6K, P90L-10K	$900.00
P9OS3BP	90000355	On-site 3 Year Service Plan for P90L-BP240	$400.00
P9OS5BP	90000356	On-site 5 Year Service Plan for P90L-BP240	$950.00
P90L5SPBP2	90000946	Extended 5 Year Factory Warranty for P90L-BP240	$700.00

Standard 3 Year Factory Warranty – 3 years electronics/battery. Telephone technical support. Depot exchange. Ground shipment one way.

Extended 5 Year Factory Warranty – 5 year electronics/battery. Telephone technical support. Advanced exchange. Pricing is limited to the continental USA. Ground shipment both ways.

On-site 3 Year Service Plan – 3 year on-site service. On-site startup. On-site corrective maintenance. Services performed 5 x 8.

On-site 5 Year Service Plan – 5 year on-site service. On-site startup. On-site corrective maintenance. Services performed 5 x 8.

P90L Battery Runtimes

Runtimes are shown in minutes and will vary based on battery condition, age, cycles, and ambient temperature.

Models	UPS + 1 BP		UPS + 2 BP		UPS + 3 BP		UPS + 4 BP		UPS + 5 BP		UPS + 6 BP		UPS + 7 BP		UPS + 8 BP	
Percentage load:	50%	100%	50%	100%	50%	100%	50%	100%	50%	100%	50%	100%	50%	100%	50%	100%
P90L-6K	19	9	47	20	79	34	115	50	153	66	193	84	236	102	280	121
P90L-10K	10	5	24	11	41	18	59	26	79	35	100	43	122	53	145	63

For applications requiring 3 or more battery packs, use KH model with 4A charger.